

## ADDENDUM #3

**KITSAP TRANSIT**  
**Invitation for Bids**  
***Ruth Haines Roadway Construction***  
**RFP #KT 23-815**  
**March 10, 2023**

60 Washington Ave. Ste. 200  
Bremerton, WA 98337  
Phone: 360.479.6962  
Fax: 360.377.7086

[www.kitsaptransit.org](http://www.kitsaptransit.org)



Note: All Proposers shall acknowledge the receipt of this Addendum on their Bid Form. This Addendum contains the following:

- I. Clarify Bid Documents
- II. Update Plans and Specification

### I. Clarify Bid Documents

Attached you will find the Revised Part 5: Schedule of Values. The following items have been updated:

- Revised title to read “KT 23-815 Ruth Haines Roadway Construction
- Revised Item Number 9 Saw Cutting to 470 LF
- Revised Item Number 11 Removing Asphalt Conc. Pavement to 1,100 SY
- Revised Item Number 23 to HMA CL. ½ in PG. 58H-22 and the quantity is revised to 524 Tons
- Added Line Item 76 Clearing and Grubbing

Kitsap Transit is still waiting for the DOR to make an official ruling on what Sales Tax Rules apply; Rule 170 and Rule 171. For bidding purposes, Contractors should assume sales tax will be added to the Bid Total.

### II. Update Plans and Specifications

Section 7-20.5 Payment located on page SP-48 of the project manual shall have the following sentence added to line 28, “Shoring necessary to install the stormwater detention system and ensure the parking lot HMA drivers are not disturbed, associated costs shall be included in this lump sum pay item.”

Add Standard Specification 2-01.5: “It may become necessary to cut down up to seven (7) large diameter fir trees, remove root structures and trim up tree limbs along Vetter Road Northwest. In your clearing and grubbing unit price (Bid Line Item 76) add the cost and effort necessary to remove the 7 additional large

### **ADDENDUM #3**

**diameter fir trees along Vetter Road and tree limbing, which is not specifically shown in the plan set.**

**All other terms and conditions remain the same.**

END ADDENDUM 3

Please remember to acknowledge this addendum.

**PART 5: Schedule of Values:**

Having carefully examined all documents for this Project, as well as the site of the Work, and the availability of materials and labor we, the above signed Bidder, propose to perform all Work identified herein in strict compliance with the Specifications, Plans, terms and conditions contained within the Contract Documents for the amounts set forth below:

**Kitsap Transit KT 23-815 Ruth Haines Roadway Construction**

<b>ITEM NO.</b>	<b>ITEM DESCRIPTION</b>	<b>SPEC REF.</b>	<b>EST. QTY.</b>	<b>UNITS</b>	<b>UNIT PRICE</b>	<b>AMOUNT</b>
1	Minor Change	SP 1-04.4 (1)	20,000	CALC	\$	\$
2	Construction Surveying	SP 1-05.4	1	LS	\$	\$
3	Record Drawings (Min. Bid \$2000)	SP 1-05.18	1	LS	\$	\$
4	SPCC Plan	STD 1-07.15	1	LS	\$	\$
5	Potholing	SP 7.04	5	EA	\$	\$
6	Type B Progress Schedule	SP 1-08.3	1	LS	\$	\$
7	Mobilization	STD 1-09.7	1	LS	\$	\$
8	Project Temporary Traffic Control	SP 1-10	1	LS	\$	\$
9	Saw Cutting	SP 2-02.3	470	LF	\$	\$
10	Removal of Structures and Obstructions	SP 2-02.3	1	LS	\$	\$
11	Removing Asphalt Conc. Pavement	SP 2-02.3	1,100	SY	\$	\$
12	Removing Cement Conc. Pavement	SP 2-02.3	65	SY	\$	\$
13	Removing Cement Conc. Curb and Gutter	SP 2-02.3	65	LF	\$	\$
14	Removing Cement Conc. Sidewalk	SP 2-02.3	42	SY	\$	\$
15	Ditch Excavation Incl. Haul	STD 2-03	55	CY	\$	\$
16	Roadway Excavation Incl. Haul	STD 2-03	326	CY	\$	\$

17	Select Borrow Incl. Haul	STD 2-03	616	CY	\$	\$
18	Structure Excavation Class B Incl. Haul	STD 2-09	530	CY	\$	\$
19	Shoring or Extra Excavation Cl. B	STD 2-09.3	1,290	SF	\$	\$
20	Trimming and Cleanup	STD 2-11	1	LS	\$	\$
21	Gravel Base	STD 4-02	486	TN	\$	\$
22	Crushed Surfacing Top Course	STD 4-04	261	TN	\$	\$
23	HMA CL. 1/2 in. PG. 58H-22	STD 5-04	524	TN	\$	\$
24	Cement Conc. Pavement	SP 5-05	65	SY	\$	\$
25	Underdrain Pipe 6 In. Diam.	STD 7-01	321	LF	\$	\$
26	Gravel Backfill for Drains	STD 7-01	119	CY	\$	\$
27	Schedule A Storm Sewer Pipe 12 in. Diam.	STD 7-04	109	LF	\$	\$
28	Testing Storm Sewer Pipe	STD 7-04	430	LF	\$	\$
29	Catch Basin Type 1	STD 7-05	7	EA	\$	\$
30	Catch Basin Type 2 48 In. Diam.	STD 7-05	1	EA	\$	\$
31	54" Diam. Control Structure w/ Solid Locking Lid	SP 7-05.2(A)	1	EA	\$	\$
32	River Rock	SP 7-06	3	CY	\$	\$
33	1 in Water Meter Service W/ Double Check Valve Assembly	SP 7-10	2	EA	\$	\$
34	Moving Existing Hydrant	STD 7-14	1	EA	\$	\$
35	Stormwater Detention System Complete	SP 7-20	1	LS	\$	\$
36	Erosion/Water Pollution Control	SP 8-01	1	LS	\$	\$
37	ESC Lead	SP 8-01	60	DAY	\$	\$
38	Check Dam	STD 8-01	16	LF	\$	\$
39	Silt Fence	STD 8-01	1,040	LF	\$	\$

40	Inlet Protection	STD 8-01	11	EA	\$	\$
41	Topsoil Type A	SP 8-02	228	CY	\$	\$
42	Bioretention Amended Soil	SP 8-05 & 9-14.5(10)	163	CY	\$	\$
43	PSIPE Acer circinatum / Vine Maple	SP 8-02	6	EA	\$	\$
44	PSIPE Pseudotsuga mensiesii / Douglas Fir	SP 8-02	2	EA	\$	\$
45	PSIPE Ribes sanguineum / Red-Flowering Current	SP 8-02	3	EA	\$	\$
46	PSIPE Tilia cordata / Little- Leaf Linden	SP 8-02	23	EA	\$	\$
47	PSIPE Brachyglottis greyii 'Sunshine' / Daisy Bush	SP 8-02	13	EA	\$	\$
48	PSIPE Nandina domestica 'Moon Bay' / Moon Bay Nandina	SP 8-02	174	EA	\$	\$
49	PSIPE Gaura lindheimer 'Siskiyou Pink' / Pink Beeblossom	SP 8-02	202	EA	\$	\$
50	PSIPE Juncus effusus / Common Rush	SP 8-02	244	EA	\$	\$
51	PSIPE Juncus tenuis / Slender Rush	SP 8-02	82	EA	\$	\$
52	PSIPE Scirpoides microcarpus / Small- Flowering Bulrush	SP 8-02	82	EA	\$	\$
53	PSIPE Rosa Rugosa "Dwarf Pavement Series' / Dwarf Rosa Rugosa	SP 8-02	247	EA	\$	\$
54	PSIPE Iris variety / Reblooming Tall-Bearded Iris	SP 8-02	40	EA	\$	\$
55	Sandy Loam	SP 8-02	54	CY	\$	\$
56	Bark Mulch	SP 8-02	41	CY	\$	\$
57	Eco-Lawn	SP 8-02	1,121	SY	\$	\$
58	Irrigation System Complete	SP 8-03	1	LS	\$	\$

59	Irrigation 4" Diameter Sleeve	SP 8-03	220	LF	\$	\$
60	Cement Conc. Traffic Curb and Gutter	STD 8-04	725	LF	\$	\$
61	Cement Conc. Pedestrian Curb	STD 8-04	20	LF	\$	\$
62	Cement Conc. Driveway Entrance Type III	STD 8-06	38	SY	\$	\$
63	Coated Chain Link Fence 4' Tall	SP 8-12	45	LF	\$	\$
64	Monument Case and Cover	STD 8-13	2	EA	\$	\$
65	Cement Conc. Sidewalk	STD 8-14	8	SY	\$	\$
66	Cement Conc. Curb Ramp Type Single Direction	STD 8-14	2	EA	\$	\$
67	Detectable Warning Surface	STD 8-14	32	SF	\$	\$
68	Electrical Service Relocation and Vault	SP 8-20	1	LS	\$	\$
69	Illumination System Complete	SP 8-20	1	LS	\$	\$
70	Permanent Signing	STD 8-21	1	LS	\$	\$
71	Painted Double-Yellow Center Line	STD 8-22	360	LF	\$	\$
72	Plastic Stop Line	STD 8-22	60	LF	\$	\$
73	Plastic Traffic Arrow	STD 8-22	9	EA	\$	\$
74	Rockery Retaining Wall	SP 8-24	94	SF	\$	\$
75	Bollard Type 2	SP 8-30	3	EA	\$	\$
76	Clearing and Grubbing	STD 2-01	0.66	AC	\$	\$
			<b>TOTAL</b>			\$